



Client: SPLASHBLADE PRODUCTS LTD
BROADFIELD HOUSE
BROADFIELD ROAD
SHEFFIELD
S8 0XJ

Order No: Verbal Gary Daly

Test Date: 23/04/2009

Certified 
Authorised Signatory **B.R.ANCLIFF**

Results of Load Tests applied to one aluminium Splashblade and four Splashblade magnets

Method of Test.

The splashblade was attached to a row of ceramic tiles which in turn were fastened to a 20mm thick chipboard frame. This test sample was supplied by the client. Tests were then carried out using a calibrated load cell and digital readout with the following results.

Test 1: Test on four splashblade magnets, folded on to a section of shower curtain.

The magnets and shower curtain were attached to the splashblade. The load required to pull the shower curtain and magnets away from the splashblade was 0.8 kg

Test 2 : Test to pull the splashblade away from the ceramic tiles.

The load required to pull the top end of the splashblade away from the ceramic tiles was 72.5kg.

Test 3 : Test to push the splashblade away from the ceramic tiles.

The load required to push the splashblade away from the ceramic tiles was 102.0kg.

END OF CERTIFICATE

This certificate is issued in accordance with the laboratory accreditation requirements of the United Kingdom Accreditation Service. It provides traceability of measurement to recognised national standards, and to units of measurement realised at the National Physical Laboratory or other recognised national standards laboratories. If, upon reproduction, only part of this report is copied, STL will not bear any responsibility for content, purport and conclusions of that reproduction. This report has legal value only when printed on STL paper and furnished with an authorised signature. Digital versions of this report have no legal value. The Terms & Conditions of STL (to be found at www.sheffieldtesting.com) are applicable on all services provided by STL.